

# Future Land Use and Sustainable Remediation at the Sydney Tar Ponds and Coke Oven Sites: A Case Study and Lessons Learned on Adaptive Remedial Design



Dan MacDonald, P.Eng., CBCL

**AECOM**



**CBCL LIMITED**  
Consulting Engineers



# Cape Breton Island





# Sydney Steel Plant

**1899 – begin construction.**

**1901 – largest North American steel mill begins production.**

**1912 – steel mill is producing half of the steel made in Canada.**



*Dominion Tar and - 91-576-225*

# History of the Site

Employed ~ 6,000 workers at its peak.

Produced mainly rails; 1st global producer of shatter free rails.





# The Legacy Contaminated Site



- 100 years of coking operations
  - Tar Ponds: 81 acres
  - 700,000 tonnes of PAH contaminated sediments
  - 45,000 tonnes of PCB contaminated sediments
- Coke Ovens: 178 acres
  - 3,000 tonnes of PAH & VOC contaminated soil
  - 25,000 tonnes of coal tar in tar cell



# Previous Clean-up Attempts

Two failed clean-up attempts:

1. Sydney Tar Ponds Incinerator
2. Encapsulation

Mandate: to get unanimous consensus for method of clean-up

Framework:

- Roundtable
- Working groups
  - Health and Safety
  - Environmental
  - Engineering
- Public meetings (>1000 over 5 years)



# Previous Clean-up Attempts

## Tar Ponds Incinerator

Tar Ponds  
Incinerator



Sludge  
Delivery  
Line



# Previous Clean-up Attempts

## Tar Ponds Encapsulation

Slag pile was to be pushed into Pond





# Joint Action Group (JAG)

The Joint Action Group (JAG) formed

- 1996 - Federal and provincial ministers meet to consider community-based process to find acceptable solutions.
- 1998 - Three levels of government and JAG sign an MOU.
- 1999 - Ottawa, Nova Scotia, and Cape Breton Regional Municipality sign \$62-million cost sharing agreement to fund scientific studies, surface clean-up and JAG activities.



# Remedial Action Evaluation Reports (RAER)

## Purpose:

To identify potential solutions for the clean up of both the Coke Ovens site and the Tar Ponds site

## Report to discuss:

- Description of clean up technology
- Construction methodology
- Order of magnitude costing
- Conceptual schedule
- Economic benefits

Report not to make recommendations or select option

Selection of clean up technology to be made by JAG



# Preliminary Engineering Design

Carried out preliminary engineering on selected clean up technologies from JAG/RAER

## Tar Ponds

- Stabilization and solidification PAH impacted sediments
- Incineration PCB impacted sediments
- Final capping

## Coke Ovens

- Interception barrier
- Groundwater collection & treatment
- Surface water control
- Final Cap

(2006 by EarthTech (now AECOM) and CBCL Limited)

# Preliminary Remedial Works

The following remedial works were carried out by the Sydney Tar Ponds Agency in preparation for the major clean up remediation:

- Relocation Coke Oven Brook
- Relocation City Water Line
- Battery Point Barrier
- Cooling Pond\*

\*First Nations set aside



# Battery Point Barrier and Cooling Pond


Cooling  
Pond




# Coke Ovens



Brook  
Realignment




Relocated  
Waterline





# Solution





# Project Schedule

- Detailed Design Started in October 2006
- Construction Commenced in 2008
- Construction Completion Scheduled for 2014 – complete in 2013





# Solidification / Stabilization



# General S/S Approach



- Control incoming flows from Coke Oven/Wash Brook by diverting them around the work area
- Control water coming from other sources using barriers
- Create a new channel within the isolated areas
- Complete in situ treatment of tar ponds sediments through solidification/stabilization
- Cap S/S treated Sediments



# Solidification and Stabilization Steps to Completion

- Characterization
- Design Criteria
  - Environmental
  - Future land use
  - GSR/LEB/fish enhancement
- Bench Scale Testing
- In-Situ Pilot Scale Testing
  - Mix Optimization
- Tender
- Full Scale Construction





# S/S Site Specific Acceptance Criteria

| Property               | Test Method   | Criteria  |
|------------------------|---|---|
| Strength (UCS)         | ASTM D 1633 Method B  | = or > 0.17MPa (25psi)  |
| Hydraulic Conductivity | ASTM 5084 (Flex Wall)   | < or = $1 \times 10^{-6}$ cm/sec  |
| Leachate               | Modified SPLP 1312 (as monolithic structural integrity procedure) | Site Specific Leachate Criteria based on MCP GW 3 (ceiling values apply) and pre/post leachate comparison |

# Implementation – Stabilization and Solidification of Sydney Tar Pond Contaminated Sediments



- Water Control
- Mechanical Mixing
- Data Collection / Verification



# Water Control: Pumping Stations – Multiple Stages



## Staged


Minimum Flow  
0 L/second

Median Flow  
400 L/second

Peak Flow  
14,000 L/second

# Sources of Water

**Tide, Sydney Harbour, Wash Brook  
& Coke Oven Brook**





# Water Collection and Pumping

- Barriers: Sheet Pile walls, berms
- Collection: Sumps, Fish Protection
- Pumping ~ 500-800 m



# Stabilization and Solidification

- The dryer the contaminants, the less cement is used, thus lowering the overall costs.
- Too dry and it is too difficult to mix.





# Data Management


| Date Treated               | Cell Number | Treated Area (sq.m) | Quantity of Sediments Treated (cu.m) | Quantity of Import Treated (cu.m) | Total Material Treated (cu.m) | Model Estimates (cu.m) (Sediments) | In field %Variation from Model |
|----------------------------|-------------|---------------------|--------------------------------------|-----------------------------------|-------------------------------|------------------------------------|--------------------------------|
| 14-Dec-09                  | 50077       | 68.719              | 171.04                               | 0.00                              | 171.04                        | 137.00                             | 24.85%                         |
| 14-Dec-09                  | 50081       | 125.678             | 202.47                               | 0.00                              | 202.47                        | 205.00                             | -1.23%                         |
| 14-Dec-09                  | 50083       | 92.729              | 193.71                               | 0.00                              | 193.71                        | 184.00                             | 5.28%                          |
| 14-Dec-09                  | 50085       | 94.248              | 193.96                               | 0.00                              | 193.96                        | 184.00                             | 5.41%                          |
| 14-Dec-09                  | 50086       | 143.157             | 201.99                               | 0.00                              | 201.99                        | 207.00                             | -2.42%                         |
| 14-Dec-09                  | 50087       | 58.625              | 142.87                               | 0.00                              | 142.87                        | 61.00                              | 134.21%                        |
| 15-Dec-09                  | 50088       | 66.608              | 165.59                               | 0.00                              | 165.59                        | 129.00                             | 28.36%                         |
| 15-Dec-09                  | 50089       | 87.598              | 166.52                               | 0.00                              | 166.52                        | 158.00                             | 5.39%                          |
| 15-Dec-09                  | 50090       | 98.196              | 185.20                               | 0.00                              | 185.20                        | 191.00                             | -3.04%                         |
| 15-Dec-09                  | 50092       | 61.465              | 135.28                               | 0.00                              | 135.28                        | 58.00                              | 133.24%                        |
| 15-Dec-09                  | 50095       | 134.050             | 193.3                                | 0.00                              | 193.30                        | 168.00                             | 15.06%                         |
| Weekly Total               |             | 1031.07             | 1951.93                              | 0.00                              | 1951.93                       | 1682.00                            | 16.05%                         |
| December - Time & Material |             | 363.85              | 870.22                               | 281.16                            | 1151.38                       | 852.00                             | 2.14%                          |
| December - Contract        |             | 3888.94             | 8315.00                              | 0.00                              | 8315.00                       | 6666.00                            | 24.74%                         |
| South Pond Total to date   |             | 8115.87             | 16989.21                             | 2631.02                           | 19620.23                      | 15603.00                           | 8.88%                          |

The Total % of Area completed of the South Pond is 6.24%

\*\*Note: High in field % variations are due to the additional material generated from TP6A ditch construction

Estimated (DTM) Quantity Remaining inside of the Berm as of Dec 18, 2009  
7660 cu.m

Highlighted by red color is revision-1



NOTES:

LEGEND:

- 1.0m Contour (Limit of S/S Treatment)
- TREATED AREA NOV 02 to DEC 04
- TREATED AREA DEC 07 to 11
- TREATED AREA DEC 14 to 18
- LOCATION OF TEST/CENTER COORDINATE

This drawing has been prepared for the use of AECOM's client and is not to be used, reproduced or relied upon by third parties, except as stated by AECOM and its client. AECOM does not warrant the accuracy, completeness, or reliability of the information contained herein, and AECOM shall not be liable for any damages, including consequential damages, arising from the use of this drawing. The drawing shall not be used for any purpose other than that for which it was prepared.

| Revision or Issue |                                |          |    |
|-------------------|--------------------------------|----------|----|
| No.               | Description                    | Date     | By |
| 1                 | Issued for review and approval | 12/18/09 | EC |
|                   | Revised quantities are changed |          |    |

Remediation of the Tar Ponds and Coke Ovens Sites

TP-6B AS-BUILT  
CONSTRUCTION PROGRESS  
REPORTED FOR AS OF DEC14-09  
to DEC18-09



| AECOM |      |          |    |
|-------|------|----------|----|
| No.   | Rev. | Date     | By |
| 1     | 1    | 12/18/09 | EC |

# Odour Management





# Spring Construction



- Solidification & Stabilization
- Channel Construction
- Stockpiling
- Coke Ovens Brook Cleanup

## **Deliverables**

Letter hand-delivered to neighbouring residents

Radio ads (82)

Newspaper ads (4 times over three weeks)

Letter to the Editor

Online Air Facts


One-on-one communication with residents

Satisfaction survey





# Odour Concerns



Concerns peaked in May

- Odour management plan: long-term foam starting end of June
- Hotline launched in August
- Coke Ovens channel construction in October

# Odour Generating Activities

- Solidification and Stabilization
- Treated Sediments
- Importation of Coke Ovens Contaminated Soils





# Odour Management Plan

- Development of an Odour Management Plan
  - Define Roles for Contractor, Design Engineer and Client
  - Define Protocols
  - Odour Complaint Hotline



Dedicated “Odour Champion”

- Respond to Work Activities
- Ensure Adequate Supply of Odour Suppressant Products

# Odour Management Plan

- Reduce Area of Exposed Materials
- Dedicated Crew
- Acquire and Apply Control Products
- When, Where and What to Apply





# Odour Management Plan

| Activity   | Description   | Action  |
|--|---|---|
| <b>Depth Determination</b>                         | Advancing test pits   | BioSolve  |
|  | Cell associated with test pit will be solidified and stabilized within 24 hours     | High concentration BioSolve or short term foam            |
|  | Cell associated with test pit will NOT be solidified and stabilized within 24 hours | High concentration BioSolve or Long term foam or ConCover |
| <b>S/S</b>   | Within the active treatment zone  | BioSolve  |
|  | Cell will be disturbed within 24 hours  | High concentration BioSolve or short term foam            |
|  | Cell will NOT be disturbed within 24 hours  | Long term foam or ConCover                                |
| <b>Foreign Material Importation &amp; Handling</b> | During importation and handling   | BioSolve  |
|  | Material will be disturbed within 24 hours  | High concentration BioSolve or short term foam            |
|  | Material will NOT be disturbed within 24 hours                                      | Long term foam or ConCover                                |

# Odour Suppressing Foam

**Concover 180** (typical in landfill application)

**Short term foam – Rusmar 645**

- Aqueous anionic surfactant mixture

**Mid and Long term foam**


**Rusmar 900s**

- Impermeable latex-based Membrane
- Repels water
- Optional fragrance
- Application – Pneumatic Units






# Concern Response Survey (informal)



# CLC Survey Results (informal)





# Green and Sustainable Remediation



G. Langille 13

# Other Green and Sustainable Remediation (GSR) Aspects in Planning and Design

| <b>Actions</b>                        | <b>Implementation</b>   | <b>Benefits</b>  |
|---------------------------------------|---|--|
| Sequencing Plans                      | <ul style="list-style-type: none"><li>• Tar Pond contractors</li><li>• Shared site infrastructure</li></ul> | <ul style="list-style-type: none"><li>• Reduction of air emissions</li><li>• Reduces erosion</li><li>• Reduces waste/new material</li><li>• Reduces fuel use</li></ul> |
| Reuse options for Existing Structures | <ul style="list-style-type: none"><li>• Materials handling pad</li><li>• CO Brook</li></ul>                 | <ul style="list-style-type: none"><li>• Reduces demolition activities</li><li>• Reduces off-site disposal waste material</li><li>• Reduces fuel use</li></ul>          |
| Abandon subsurface structures         | <ul style="list-style-type: none"><li>• Coke Ovens Voids and underground infrastructure</li></ul>           |  |

# Green & Sustainable Remediation in Planning and Design - continued

| Actions                              | Implementation  | Benefits  |
|--------------------------------------|---|---|
| Salvage Options / Recycling Options  | <ul style="list-style-type: none"> <li>• TP2 Recycling</li> </ul>                         | <ul style="list-style-type: none"> <li>• Reduces off-site disposal of waste material</li> <li>• Reduce SS volumes</li> <li>• Recycle/reclaim scrap</li> </ul>   |
| Stockpile cover                      | <ul style="list-style-type: none"> <li>• Project Materials Management Strategy</li> </ul> | <ul style="list-style-type: none"> <li>• Reduces dust</li> <li>• Reduces erosion</li> <li>• Odour Management</li> </ul>   |
| Routinely evaluate treatment process | <ul style="list-style-type: none"> <li>• SS Process QA/QC Management</li> </ul>           | <ul style="list-style-type: none"> <li>• Reduces air emissions</li> <li>• Reduces water use and waste water discharge</li> <li>• Reduces off-site disposal waste material</li> <li>• Reduce material use</li> </ul> |



# Future Land Use

## Recreation

- Walking/cycling trails
- Green Space

## Light Commercial

## Sydney “Common” Area



# Future Land Use

## Highlights of the Plan:

### A Commons Area including:



- Sports fields
- Outdoor concert venue
- Walking trails
- Wildlife stations
- Parking area
- Urban forest

### A Greenway Trail Network with:

- Bridges
- Boardwalks
- Interpretive stations
- Outdoor exercise stations
- Rest areas


### New Roads and Sidewalks for:

- Community connectors
- Business campus
- Land banking for future growth
- Commercial expansion along SPAR road



Photos from: Ekistics Planning & Design "Former Tar Ponds Site Future Use " Sowing the Seeds of Change  
<http://www.tarpondscleanup.ca/futureuse/>





# Sydney Tar Ponds & Coke Oven Site

contour interval = 2m

scale = 1:3000

August 2009





# Sydney Tar Ponds & Coke Oven Site

contour interval = 2m

scale = 1:3000

April 2010

**PHASE 1**

**4 YEAR PLAN**





# Sydney Tar Ponds & Coke Oven Site

contour interval = 2m

scale = 1:3000

April 2010

**PHASE 2**

**FUTURE VISION**





# Local Economic Benefits

## Underlying objectives:


- To ensure that economic benefits accrued to the greatest extent possible to Cape Breton
- To realize the sustainability imperative, i.e., that real economic value, beyond the remediation itself, would endure

## Measures of success:

- Upwards of 50% of the monies have been spent in Cape Breton
- Through “set-aside” provisions, First Nations companies attained experience – now successfully competing on the open market – outstanding success
- Establishment of the Center for Sustainability in Energy and the Environment at Cape Breton University



# Sustainability Model – Tar Ponds Project





August  
2008

September  
2013



G. Langille 13

G. Langille



# Prior to Remediation



G. Langille



# Progress to Fall 2013





# Questions?

